ROI CabmateCab Suspension



Link Mfg. Ltd. 223 15th St. N.E. Sioux Center, IA USA 51250-2120 www.linkmfg.com

QUESTIONS? CALL CUSTOMER SERVICE 1-800-222-6283

OWNER'S GUIDE

Cab Suspension
INTERNATIONAL LT SERIES
SLEEPER CABS
MODEL YEAR 2017 & NEWER

LINK PART NO. 26302020





1. PLUMBING INSTRUCTIONS

AWARNING FOR SAFETY PURPOSES THE ROI CABMATE MUST BE SUPPLIED FROM A PRESSURE PROTECTED CIRCUIT. IN THE EVENT OF AN AIR LEAK IN THE CAB SUSPENSION, FAILURE TO PROVIDE A PRESSURE PROTECTED CIRCUIT MAY CAUSE LOSS OF AIR PRESSURE TO VITAL SYSTEMS ON THE VEHICLE.


AWARNING CONNECT THE ROI CABMATE DIRECTLY TO THE MAIN AIR TANK. YOU WILL NEED AN AIR PRESSURE PROTECTION VALVE IN THE LINE. (INCLUDED IN THE PRESSURE PROTECTION KIT. LINK MFG. PART NO. 13500000). DO NOT USE AN AIR PRESSURE REGULATOR!

HEIGHT ADJUSTMENTS

Measure the design height of the air spring(s). The height should be 6.75 inches. To change the height, disconnect one end of the valve linkage and adjust accordingly. Tighten the lock nuts on the valve linkage.

MAINTENANCE

The ROI CABMATE needs no lubrication and little maintenance. The following components should be checked at the time the truck is being serviced. However, immediate corrective action should be taken if a serious malfunction occurs.



COMPONENT POSSIBLE PROBLEM CORRECTIVE ACTION Airlines Air leaks Replace airline		CORRECTIVE ACTION
		Replace airline
Fittings	Air leaks	Replace fittings.
Air Springs	A. Improper height B. Air leakage C. Air springs not filling	A. Adjust valve linkage to maintain proper air spring height. B. Replace air spring. C. See "Electronic Troubleshooting" Section.
Control Box	Air spring(s) will not inflate when weight is added to the cab; OR Air spring(s) will not deflate when weight is removed from the cab.	See "Electronic Troubleshooting" Section.
Shock Absorber	Improper damping effect	A. Inspect LED for fault codes. If present, repair per "Electronic Trouble-shooting" section. B. If no faults are present, replace shocks.

AWARNING LOSS OF AIR PRESSURE TO THE ROI CABMATE WILL CAUSE SUDDEN MOVEMENT OF THE CAB. PRIOR TO INSTALLING OR PERFORMING MAINTENANCE, BLOCK UP THE CABMATE TO PREVENT THE POSSIBILITY OF INJURY.

Prior to removing the control box for servicing, perform the following:


- 1. Unplug the power harness
- 2. Unplug the shock harness
- 3. Unplug the airlines from the control box
- 4. Disconnect the position sensor

2. TORQUE INSTRUCTIONS


IMPORTANT: Periodically check the tightness of all fasteners.

TORQUE TABLE		
COMPONENT	FASTENER	TORQUE
POSITION SENSOR	M5	26-44 IN-LBS
CONTROL BOX	1/4	48-60 IN-LBS
SHOCKS	1/2	60-70 FT-LBS

3. FAULT TROUBLESHOOTING FLOW CHART



4. BLINK CODE FLOW CHART AND TABLE





Blink	Code	Fault Definition		
Blink Part 1	Blink Part 2	Component	Description	
1	2	Position Sensor	Low Voltage	
1	3	Position Sensor	High Voltage	
5	1	Fill Valve	Open Circuit	
5	2	Fill Valve	Short to Ground	
5	3	Fill Valve	Short to Battery	
5	4	Fill Valve	Over Current	
6	1	Exhaust Valve	Open Circuit	
6	2	Exhaust Valve	Short to Ground	
6	3	Exhaust Valve	Short to Battery	
6	4	Exhaust Valve	Over Current	
2	3	Accelerometer	Low Voltage	
2	4	Accelerometer	High Voltage	
3	1	PS Damper	Open Circuit	
3	2	PS Damper	Short to Ground	
3	4	PS Damper	Short to Battery	
3	5	PS Damper	Over Current	
4	1	DS Damper	Open Circuit	
4	2	DS Damper	Short to Ground	
4	3	DS Damper	Short to Battery	
4	5	DS Damper	Over Current	
LED on, n	o blinking	ECU	Unknown Failure	
Steady, slow blinking		No fault	s detected	


5. WARRANTY - Refer to www.ROlcabmate.com for warranty information and registration.

6. SERVICE KITS


	ROI CABMATE - INTERNATIONAL LT SERIES		
ITEM NUMBER	DESCRIPTION		
4CM00048	SERVICE KIT - ROI CONTROL MODULE		
4CM00051	SERVICE KIT - WIRING HARNESS, SHOCKS		
4CM00052	SERVICE KIT - WIRING HARNESS, POWER		
4CM00054	SERVICE KIT - WIRING HARNESS AND FASTENERS, CONTROL MODULE		
4CM00055	SERVICE KIT - AIRLINES WITH VALVES AND FITTINGS		
4CM00056	SERVICE KIT - POSITION SENSOR, PIVOT BALL AND FASTENERS		
4CM00057	SERVICE KIT -ACCELEROMETER WITH FASTENERS		
4CM00058	SERVICE KIT - PIVOT BALL CLAMP WITH PIVOT BALLS		
4CM00060	SERVICE KIT - ECU		
4CM00064	SERVICE KIT - ROI SHOCK ABSORBER ASSEMBLY		
4CM00069	SERVICE KIT - CAB BRACKET, RH		
4CM00070	SERVICE KIT - CAB BRACKET, LH		
29910051	SERVICE KIT - LINKAGE, MEDIUM		









4CM00052 - SERVICE KIT - WIRING HARNESS, POWER		ÆR
ITEM	DESCRIPTION	QTY
1	1 HARNESS-WIRE, POWER	




4CM0	4CM00054 - SERVICE KIT - WIRING HARNESS AND FASTENERS		
ITEM	ITEM DESCRIPTION		
1	#10 X 3/8 THREAD CUTTING SCREW	8	
2	HARNESS-WIRE, CONTROL BOX	1	




4CM	4CM00055 - SERVICE KIT - AIRLINES WITH VALVES AND FITTINGS		
ITEM	ITEM DESCRIPTION Q		
1	AIRLINE-NYLON, .250 O.D., BULK (FEET)	2	
	BRANCH TEE-PLUG-IN, 1/4"	1	
	SOLENOID-VALVE	2	
4	UNION-BULKHEAD, 1/4" TB	2	




4CM	4CM00056 - SERVICE KIT - POSITION SENSOR, PIVOT BALL AND FASTENERS		
ITEM	ITEM DESCRIPTION QTY		
1	1/4 LOCK WASHER	1	
2	1/4 UNC HEX NUT (GR B)	1	
3 BALL-PIVOT, THREADED		1	
4	M5X0.8X10 SOCKET BUTTON HD SS CAP SCREW	2	
5	SENSOR-POSITION	1	




4CM00057 - SERVICE KIT -ACCELEROMETER WITH FASTENERS		RS
ITEM DESCRIPTION		QTY
1	10-24 NYLOCK NUT, SS	2
2	10-24 x 1/2 UNC CR PH MACH SCREW, SS	2
3	ZF ACCELEROMETER ASSEMBLY	1




4CM00058 - SERVICE KIT - PIVOT BALL CLAMP WITH PIVOT BALL		LS
ITEM	ITEM DESCRIPTION (
1	1/4 X 3/4 FLANGE HEAD BOLT	2
2 BALL-PIVOT, THREADED		2
3	CLAMP-PIVOT BALL	1




	4CM00060 - SERVICE KIT - ECU		
ITEM DESCRIPTION			
1 CL449 CONTROLLER, NAVISTAR LT			





4CM00070 - SERVICE KIT - CAB BRACKET, LH			, LH
	ITEM	DESCRIPTION	QTY
	1	BRACKET-CAB	2







LINK MANUFACTURING, LTD. 223 15TH ST. NE, SIOUX CENTER, IA 51250 1-800-222-6283 www.linkmfg.com